



The European XFEL Project

Klaus Floettmann

12th International Workshop on RF Superconductivity

15th July 2005

Content



Introduction

Choice of machine parameters

Project Overview & Status


Challenges for Science with X-rays

Real-time observation
of atomic motion





Get structural information
out of single bio molecules

Enter the regime of non-linear
interaction of X-rays



Radiation Characteristics




- high brilliance



Choice of the machine parameters

Emittance from photocathode RF gun injector

Transverse Emittance



- 1nC charge
- uniform transverse distribution
- longitudinal flat-top with 2 ps rise time
- incl. thermal emittance

$$\epsilon_n = 0.9 \mu\text{m}$$

Emittance Measurement at TTF

x-plane (100% beam intensity)
 1.892 ± 0.077 (2.0)
 -1.294 ± 0.097 (-1.189)
 2.132 ± 0.177 (2.473)
 139.7 ± 7.1 (141.1)
 153.5 ± 4.1 (141.1)
 171.5 ± 7.8 (141.1)
 118.1 ± 4.2 (141.1)
 2.085 (2.0)
 0.321 (0.0)
 1.039 (1.0)

12:49:46 23.02.2005
 γ_E [mm mrad]
 α_{4DBC2}
 β_{4DBC2} [m]
 σ_{4DBC2} [μm]
 σ_{6DBC2} [μm]
 σ_{8DBC2} [μm]
 σ_{10DBC2} [μm]
 γ_{E1}, γ_{E2}
 beta beating
 B_{mag}

y-plane (100% beam intensity)
 1.826 ± 0.124 (2.0)
 1.498 ± 0.168 (1.219)
 2.584 ± 0.174 (2.545)
 137.2 ± 4.4 (143.1)
 127.0 ± 14.7 (143.1)
 138.6 ± 7.0 (143.1)
 156.9 ± 6.0 (143.1)
 1.601 (2.0)
 0.294 (0.0)
 1.033 (1.0)

1 nC

measured:


1.9 μm

simulated:


2.1 μm

(w. o.

compression)




images / screen = 20
 energy = 127.00 MeV
 charge = 1.04 nC




RF gun development at PITZ in Zeuthen

DESY DESY DESY DESY DESY




On-going program:


- increase the gradient on the cathode from 40 MV/m to 60 MV/m
- further improve the transverse and longitudinal laser profile (collab. Max-Born Institute, Berlin)



Bunch compressor




Peak current




END of LINAC with 60 slices

Slice emittance




END of LINAC with 60 slices

The 3rd harmonic section





The longitudinal phase space



Longitudinal particle distribution behind bunch compressor with and without the 3rd harmonic system.

Choice of the Beam Energy


Emittanz [mrad mm]	0.7 – 2.0
I_{peak} [kA]	5.0
ΔE [MeV]	2.5
Undulator gap [mm]	10



→ 17.5 GeV for 1 Å


Wavelength vs Accelerating Gradient

Photon wavelength vs E_{Acc} ,
reference point 1 Ångström at 17.5 GeV



Nominal linac energy 20 GeV, includes ^{57}Fe line @ 0.8Å


Operational flexibility – duty cycle



Decreasing T_{beam} at higher f_{rep} helps, but injector is an issue!

Sketch of Possible Future CW Operation Mode

If Å FEL radiation at lower beam energy comes in reach
(better injector/beam quality, advanced FEL concepts, ...)
→ high duty cycle, up to CW, can become an attractive option



Sketch of Future CW Operation Mode cont'd

**Linac layout & cryogenics consistent with this option
(at $E_{\text{Acc}} = 7 \dots 8 \text{ MV/m}$), different RF system has to be added**

Beam Energy [GeV]	6.5
Acc. Gradient [MV/m]	7
Beam Current* [mA]	0.18
Bunch Spacing [μs]	5.5
RF power / module [kW] (incl. overhead)	~ 20
Dynamic cryo. load 2 K [kW]	~ 2.4

* total beam power of 1.2 MW sufficient to operate simultaneously
4 undulator beam lines at the dump limit of 300 kW

***If user demand very high average
power, ERL option is conceivable***




Project Overview & Status

XFEL Site in Hamburg



Injector & Bunch compressor



XFEL-Cryomodule Design

based on the TESLA/TTF –type III design


8 TESLA Type Cavities

1 magnet package

Spec: 28 MV/m
operable
23 MV/m needed for
20 GeV operation



116 Modules

928 Cavities



Cryomodule cross-section

XFEL-Cryomodule Design






300 K and 2K
Module 5 coupler 2

Cavity chain is fixed to an invar rod – couplers keep position


RF System

Klystron




29 RF Stations

XFEL Tunnel Layout




Linac tunnel 15 – 30m underground in urban area

Distribution Fan




User facility - Beam lines



SASE undulators 0.1 – 6 nm, magn. Length 150 – 80 m

Variable gap (min. 10 mm) → independent λ -tuning

2 Examples for Experiments Installation



Schenefeld Site



K. Floetmann

12th Int. Workshop on RF Superconductivity

Schenefeld Site



K. Floetmann

12th Int. Workshop on RF Superconductivity

Schenefeld Site



K. Floettmann


12th Int. Workshop on RF Superconductivity

Challenges for the Machine

- Generation and Transport of High Brightness Electron Beams
 - Coherent Synchrotron Radiation
 - Surface Roughness Wakefields
- Stability
- Synchronization
- ...

Challenges for the Users


Users have to be very fast



New experimental techniques and fast detectors
have to be developed !

XFEL schedule:

Memorandum of Understanding: to date, 11 countries have decided to sign




Assume final project approval & funding at European level in
~mid 2006

Status of X-ray FEL projects


2012 European XFEL (Hamburg)



2008 LCLS (Stanford)



2004 VUV-FEL (Hamburg)



2000-2002 TTF-1 (Hamburg)
2000-2001 LEUTL (Argonne)