

**Cornell University**  
**Facilities and Campus Services**  
**Document Archive Record Full Scope**

| <b>Facility</b> | <b>Par #</b> | <b>Record #</b> | <b>Drawing #</b> | <b>Job Date</b> | <b>Project Title</b>  |
|-----------------|--------------|-----------------|------------------|-----------------|---|
| 2085            | S            |                 | D4324            |                 | Wilson Laboratory - E.R.L. Room 143 and Laser Room 147 Cooling Design |

**Full Scope**

Purpose and Need: The purpose of the project is to construct the Control Room and the Laser Room for the Wilson Lab Phase 1A Energy Recovery Linear Accelerator (ERL) Project. A portion of the Wilson Lab stockroom (Rm #141) adjacent to L0 (Location 0) and the ERL prototype site will be renovated for this purpose and will convert 324 gross square feet for the ERL Control Room (Rm #147) and 162 gross square feet for the ERL Laser Room (Rm #143). The ERL Project will upgrade the current Cornell Energy Storage Ring (CESR) accelerator to far higher performance by converting its operation to an Energy Recovery Linac technology. This project is needed because the best x-ray science can only be done on a state-of-the-art x-ray source. The ERL machine will serve as a far brighter light source than the current facility and will be the first world-wide demonstration of ERL technology for producing x-rays of outstanding quality for making the best microbeams, highest coherence, and short pulses available for x-ray science purposes. The National Science Foundation (NSF) has awarded Cornell funds to begin development of the new, advanced synchrotron radiation x-ray source, called ERL. The NSF award to Cornell funds prototyping of critical components of the ERL at the Wilson Synchrotron Lab and thus both the ERL Control Room and ERL Laser Room are immediate early project needs to support the completion of the Prototype ERL (Phase 1A). Prototype construction and testing is expected to be completed in 2008. Cornell then will seek funding for a full-scale ERL facility (Phase 2).

Scope of Work: The scope of work for this PAR includes the following: Provide final design and construction documents for the Wilson Lab ERL Control Room 143 and ERL Laser Room 147. Design is complete and the costs will be transferred to this capital project. Prepurchase long lead equipment, including: ceiling system, doors and frames, fabric panels, two (2) fan coil units with condensers, sheet metal constant air volume box, supply air diffusers, lights and dimmers, and fire alarm devices. Provide demolition of mechanical and electrical components. Provide general construction, walls, doors, ceiling & room finishes. Only the Laser Room will include a new suspended ceiling. Complete mechanical HVAC renovations including constant air ventilation, high efficiency air filtration for the Laser Room, separate DX cooling and reheat systems for the Control Room and Laser Room. Air cooled condensers will be located just off the loading dock adjacent to Room 145. Provide and install electrical systems including lighting, power to mechanical equipment, and fire alarm devices.